
## NPR 7120.5E NASA Project Life Cycle

Approval for Appro








#### **One Landsat in Orbit**

LDCM

- Landsat 5 was officially "retired" when deorbiting and decommissioning began on January 15, 2013
  - Launched in 1984, Landsat 5 exceeded its 3 year design life by 25 years.
- Landsat 7 is still collecting global data
  - Launched in 1999 with a 5 year design life, the Landsat 7 mission is about to begin its 14<sup>th</sup> year.
  - Robust global acquisitions are continuing.
  - ETM+ 2003 scan-line corrector failure means 22 percent of each scene is missing.
  - Fuel-based end-of-life is 2017.




### **Successfully Completed Observatory Environmental Testing**



EMI/EMC Aug. 2012



Dynamics Sept. 2012





Thermal Vacuum Oct-Nov 2012



### **Observatory Status and Readiness**

#### Observatory Shipment to VAFB

 Successful Pre-Ship Review 12/14-15 & arrived at VAFB on 12/19

## Observatory post-ship activities proceeding as planned

- Post-shipment Comp. Perf. Test completed
- Pad Aliveness Test dry run completed
- Solar Array First Motion, Re-stow, & current measurements completed
- Solar Array NEA flight installation & electrical verification completed
- Prop functional & fueling completed
- Mate to PLA completed
- Battery reconditioned
- Observatory encapsulated into LV fairing
- Transported to pad 1/25 and mated to LV
- Successful Pad Aliveness test completed


#### **Observatory On Track For Launch!**



### **LDCM Transporter**

#### LDCM

- LDCM Transporter completed fabrication in July 2012 by Nelson Manufacturing in Ohio
- A successful "Pathfinder" dry-run trip was made from Orbital to VAFB in August
- Removable front and rear bogies
- Hydraulically adjustable ride height (0"- 12")
- Air bearing equipped center section
- Environmentally controlled
- Live wirelessly monitored parameters
- 13'-9" tall x 14'-8" wide x 80' long and 115,000 lbs









## **LDCM Observatory En Route**

LDCM

Leaving Orbital facility



Arriving at Vandenberg



**LANDSAI** Data Continuity Mission Launch

Safe in the processing facility







## **Settling into Launch Processing**







**LANDSAT Data Continuity Mission Launch** 

## **Encapsulation**











#### **Atlas V Launch Vehicle**






#### **Vehicle Configuration**

- Atlas V 401 (AV-035)
  - 4 Meter Extended Payload Fairing (EPF)
  - Centaur w/ Single RL10A-4-2 Engine
  - Core Atlas Booster w/ RD-180 Engine
  - C22 Launch Vehicle Adapter
  - D1666 Payload Support Ring
  - LSPSS 1666 Separation System
  - On-board Video System
- LDCM will be
  - 36<sup>th</sup> Atlas V launch
  - 6<sup>th</sup> Atlas V from VAFB
  - 16<sup>th</sup> Atlas V 401 configuration
  - 9<sup>th</sup> NASA Atlas V mission
  - 1<sup>st</sup> NASA Atlas V launch from VAFB





# Space Launch Complex -3 (SLC-3)







# First Stage Booster & RD-180 Engine







**LANDSAT Data Continuity Mission Launch** 

## Interstage Adapter and Centaur Upper Stage





## **Fairing Lift**











## **Ground System Element Readiness (1/3)**

DCM

- Mission Operations Element (MOE)
  - Includes command/control, mission planning, flight dynamics, off-line trending/analysis
  - Final delivery (Build 5.0.5) installation & testing complete
  - MOE is ready for Launch / Commissioning
- Collection Activity Planning Element (CAPE)
  - Generates daily LDCM science imaging schedule
  - Final delivery (Build 3.1) installation & testing complete
  - CAPE is ready for Launch / Commissioning
- Spacecraft/Observatory Simulator (SOS) and Softbench Simulators
  - Simulators up-to-date with latest Flight Software & databases
  - Continuing to investigate 1 open issue
    - Simulators do not accurately model EPS
  - Simulator EPS issue is fully mitigated for launch and early orbit via extensive on-site
     Orbital support. Plan to implement long-term solution by L + 60 days
  - SOS and softbenches are ready for Launch / Commissioning



## **Ground System Element Readiness (2/3)**

- Ground Network Element (GNE)
  - Completed LDCM-specific hardware upgrades at all LDCM ground stations
  - Final software delivery (Build 5.1) integration & testing complete
  - Executed several connectivity tests & proficiency exercises between MOC & each station
  - GNE is ready for Launch / Commissioning

Landsat Ground Station (LGS) USGS/EROS, Sioux Falls, SD



Gilmore Creek station (GLC)
Gilmore Creek, AK



SG 2 (SKS)
SG 3
SG 4 (IPO)
SG 3
CDA 1
(EUM)
CDA 2 (EUM)

Svalbard Ground Station (SGS) Svalbard, Norway

## **Ground System Element Readiness (3/3)**

**DCM** 

- Data Processing and Archive System (DPAS)
  - Located at USGS/EROS facility, Sioux Falls, SD
  - Performs science data ingest, processing, archival, and distribution
  - Completed all algorithm development
  - Demonstrated ability to process data directly from observatory
  - Final delivery (Build 4.1) integration & testing complete
  - DPAS is ready for Launch / Commissioning








## Mission Operations Center / Launch Support Room

- Mission Operations Center (MOC); GSFC Bldg. 14
  - Flight Operations Team performs all flight operations functions here
- Launch Support Room (LSR); GSFC Bldg. 14
  - Used by Flight Support Team from launch end of commissioning
- MOC & LSR extensively exercised during Observatory I&T, Mission Readiness Tests, Mission Operations Simulations, & Launch Rehearsals
- MOC & LSR ready for Launch / Commissioning




#### **LDCM Launch Team**

Legend:

Room (LSR)


Mission Ops

- Led by LDCM Mission Manager
- Consists of:
  - Flight Support Team (FST)
    - Engineering team supporting LFO&A
      - Includes: Orbital, BATC, TIRS & Project Engineers
    - Led by FST Lead (FSTL) oversees execution of mission timeline
  - Flight Operations Team (FOT)
    - Executes/conducts flight operations for life of mission



#### Launch Decision Flow


#### LDCM





#### **Atlas V Launch Vehicle**





#### **Vehicle Configuration**

- Atlas V 401 (AV-035)
  - 4 Meter Extended Payload Fairing (EPF)
  - Centaur w/ Single RL10A-4-2 Engine
  - Core Atlas Booster w/ RD-180 Engine
  - C22 Launch Vehicle Adapter
  - D1666 Payload Support Ring
  - LSPSS 1666 Separation System
  - On-board Video System
- LDCM will be
  - 36<sup>th</sup> Atlas V launch
  - 6<sup>th</sup> Atlas V from VAFB
  - 16<sup>th</sup> Atlas V 401 configuration
  - 9th NASA Atlas V mission





#### **Mission Parameters**




Launch Vehicle Configuration:	Atlas V 401
Launch Site:	WR SLC-3E
Launch Date/Time:	11 February 2013 / *10:02:00 PST (18:02:00 GMT)
Spacecraft Mass:	2823.6 kg (6225 lbm)
Launch Window:	*Single 48 min opportunity each day, any day, beginning with the opening of the launch window
Flight Azimuth:	186.39 deg
Free Molecular Heating (FMH) at PFJ:	≤ 1135 W/m <sup>2</sup>
Thermal Conditioning Roll During Coast:	1.0 +/- 0.5 deg/sec
Sun Angle Requirement During Coast:	LV +X axis perpendicular to the Sun Vector within +/-5 deg
LDCM Targets at 1st Descending Node: Apogee: Perigee: Inclination: Mean Local Time/Descending Node:	685 +/- 10 km 685 +/- 10 km 98.22 +/- 0.09 deg 10:11 am +/- 1 min
Centaur Disposal:	3 <sup>rd</sup> burn to achieve Earth-escape velocity



## **Optimal Flight Profile**








#### Groundtrack





STATION IDENTIFICATION (Acquisition Elevation 1.5 Degrees)
WR = Western Range Telemetry Stations (VTS)
HULA = Hawaii Tracking Station (HTS)
TDRS = NASA Tracking and Data Relay Satellite
LION = AFSCN Station at Oakhanger
POGO = AFSCN Station at Thule





